

“काम छोडाऔ, स्कूल पठाऔ”

# श्रीपुर्राज सामुदायिक विकास केन्द्र, सप्तरी

SHRIPURRAJ COMMUNITY DEVELOPMENT CENTER (SCDC) SAPTARI

Kushaha-2, Saptari

## शिलबन्दी कोटेशन सम्बन्धमा

सुचना नं २०८२/०८३/१५

(पहिलो पटक प्रकाशित मिति २०८३/०९/१०)

१. श्रीपुर्राज सामुदायिक विकास केन्द्र, सप्तरी गैर सरकारी तथा गैर नाफामुलक संस्था हो, द फ्रिडम फण्डको आर्थिक सहयोगमा संस्थागत विकास अन्तर्गत यस संस्थाको कार्यालयको भवन निर्माण दोश्रो चरणको कार्य गर्नु पर्ने भएको, उल्लेखित कार्यको लागि इजाजत प्राप्त इचछुक फर्म/संस्था/निर्माण कम्पनीहरुको लागि देहायको शर्तहरुको अधिनमा रही तोकिएको समयभित्र रितपूर्वकको पहिलो पटक ०७ दिने शिलबन्दी कोटेशन आव्हानको सुचना प्रकाशित गरिएको छ।  
शिलबन्दी कोटेशन विवरण

प्याकेज नं.	गर्नुपर्ने कार्यहरु विवरण
१	Septic tank & Soak pit Construction work
२	Plaster, Painting, flooring work

शर्तहरु :

१. शिलबन्दी कोटेशन फारम प्रथम पटक सुचना प्रकाशित भएको मितिले ७ औं दिनभित्र कार्यालय समयमा नविकरण भएको फर्मको सही छाप, सही गरिएको र लाहा छाप भएको कोटेशन श्रीपुर्राज सामुदायिक विकास केन्द्र ( SCDC), सप्तरीको सम्पर्क कार्यालय खडक नगरपालिका-६, कल्याणपुर सप्तरीमा मिति २०८३/०९/१६ गते ४:०० बजे भित्र बुझाउनु पर्नेछ। तोकिएको समयभित्र नआएको कोटेशन मान्यता दिइने छैन। स्पष्टसँग बुझिने गरी खामको बाहिरपट्टि मैटल सिल वीन भनी उल्लेख गरिएको हुनु पर्नेछ। यो बोलपत्र मिति २०८३ साल वैशाख १७ गते अपरान्ह १.०० बजे खोलिने छ।

२. प्रथम पटक सुचना प्रकाशित भएको मितिले ८ औं दिन वैशाख १७ गते अपरान्ह १.०० बजे खोलिने छ। दरभाउपत्र दाता वा निजको प्रतिनिधीको रोहवरमा खोलिनेछ। दरभाउपत्र दाता वा प्रतिनिधी उपस्थिती नभएमा दरभाउपत्र खोल्न बाधा पर्ने छैन। दरभाउपत्र खरिद वा दाखिला गर्ने अन्तिम दिन सार्वजनिक बिदा परेमा उक्त दिनको लगतै(कार्यालय खुलेको दिन) सोहि समयभित्र दाखिला गर्न सकिनेछ।

३. दरभाउ पेश गर्दा प्रत्येक आइटममा अंक र अक्षर दुवैमा प्रष्ट लेखनुपर्छ। जम्मा जोड गरेको रकम लेख्नु पर्नेछ। दररेट मात्र लेखी बोलपत्र बुझाएमा उक्त बोलपत्र रद्द गरिनेछ।

५. रित नपुगी आएका वा म्याद गुज्री आएको वा शर्त राखि केरमेट गरिएको तथा टिपेक्स लगाएको कोटेशनलाइ मान्यता दिइने छैन।

६. कोटेशन पुर्ण वा आंशिक रुपमा स्विकृती गर्ने वा रद्द गर्ने अधिकार यस कार्यालयमा निहित हुने छ।

७. कोटेशन फारमको साथमा आपूर्ति कर्ताले निम्न कागजातहरु पेश गर्नु पर्ने छ।

i. फर्म/निर्माण कम्पनीको दर्ता प्रमाण पत्रको प्रतिलिपी

ii. आ.व. २०८१/२०८२ को कर चुक्ताको प्रमाण पत्रको प्रतिलिपी

iii. PAN /VAT मा दर्ता भएको प्रमाण पत्रको प्रतिलिपी

८. थप जानकारीको लागि कार्यालय समभित्र कार्यालयको टेलिफोन नम्बर ०३१-५४०४१२ मा सम्पर्क गर्न सकिनेछ। यो सुचना यस कार्यालयको Website : [www.shripurraj.org.np](http://www.shripurraj.org.np) तथा Bill of Quantities समेत प्रकाशन गरिएको छ।

९. यस कार्यालयले प्रतिपादन गरेको आचारसहिता तथा निति नियमहरु आपूर्ति कर्ताले पालना गर्नु पर्ने छ।

फर्म/ निर्माण कम्पनीके नाम:

सप्लायर्सको नाम :

टेलफोन नम्बर :

दस्तखत :

ठेगाना :

मिति तथा छाप :

“काम छोडाऔ, स्कूल पठाऔ”

## श्रीपूरज सामुदायिक विकास केन्द्र, सप्तरी

SHRIPURRAJ COMMUNITY DEVELOPMENT CENTER (SCDC) SAPTARI

Kushaha-2, Saptari

---

## Bill Of Quantity(BOQ)

Owner :-Shreepuraj Community Development Center (SCDC),Saptari  
Name of project :- Office Building Construction.(second phase)

Project Period:2 Months  
F.Y.: B.S. 2082/2083

Item No.	Description	Quantity	Unit	Rate per Unit. NPR. (Excluding VAT)		Amount NPR.	Remarks
				In Figure	In Words		
1	Site clearance before of construction works	1.000	Job				
2	Back filling with ordinary soil by spreading it in the layer of 15-15cm,sprinkling water and ten compacting with the help of labour including hauling distance up to 10m. all complete.	409.686	Cum.				
3	Flat Brick Solling work with sand packing levelling and rammimn with water spray all complete.	33.841	Sqm				
4	Plain Cement concreta PCC M15 (1:2:4) in foundation and floors with cement sand and crused aggregate of 10mm to 38mm gauge including miximn with mixture machine and , laying in line & level with curing all type of works complete as per specification & instruction.	3.384	Cum.				
5	First class local chimney brick work in cement sand mortar (1:4) in foundation in perfect line & level including wetting the brick,packing the joints & curing all types of works as per specification & instruction by Engineer.	1.250	Cum.				
6	12.5 mm. thick cement sand plaster work (1:4 ) on wall and floor etc.	99.988	Sqm				
7	38 mm. thick Flooring (1:2:4)with neat cementpunning in flooring area as per instruction	105.219	Sqm				
8	Two coat washeble Distemper paint of approved colour and shade over one coat primer on plaster surface including cleaning and scaffolding all complete as per specification and instruction.	733.265	Sqm				
9	Two coat Weather Guard Paint of approved colour and shade over one coat primer on plaster surface including cleaning and scaffolding all complete as per specification and instruction.	195.589	Sqm				
10	6 mm.Th. Porcelain Tiles white/coloured in dado, skirting etc. laid with cement sand mortar 1:4 with white cement slurry including polishing to smooth finished glazed surface as per instruction & specification all complete work.	18.601	Sqm				
11	Supplying and applying two coat of Enamel paint approved quality and colour over porperly cleaned surface and primmer coat all complete. As per specification and instruction of site engineer	49.699	Sqm				
12	Supplying and applying Metal Squire Rod for Windows Grill with primmer coat all complete. As per specification and instruction of site engineer ( per sqm= 15.00kg)	277.725	kgs				
13	Supplying and fixing of 50mm dia. Stainless stell staircase Railing all completw work.	12.000	Sqm				
14	Supplying and fixing of Aluminium casement doorfor Toilet	3.000	Sqm				
<b>Total cost Rs.</b>							

Name of firm Address :-  
Sign.

Stamp of firm

## Bill Of Quantity(BOQ)

Owner :-Shreepuraj Community Development Center (SCDC),Saptari

Project Period:2 Months

Name of project :- Septictank & Soakpit Construction work.

F.Y.: B.S. 2082/2083

Item No.	Description	Quantity	Unit	Rate per Unit. NPR. (Excluding VAT)		Amount NPR.	Remarks
				In Figure	In Words		
1	Site clearance before of construction works	1.000	Job				
2	Earth work excavation in foundation in B/M soil.	8.683	Cum.				
3	Flat Brick Solling work with sand packing levelling and rammimn with water spray all complete.	14.557	Sqm				
4	Plain Cement Concrete PCC M15 (1:2:4) in foundation and floors with cement sand and crussed aggregate of 10mm to 38mm gauge including miximn with mixture machine and , laying in line & level with curing all type of works complete as per specification & instruction.	2.033	Cum.				
5	First class local chimney brick work in cement sand mortar (1:4) in foundation in perfect line & level including wetting the brick,packing the joints & curing all types of works as per specification & instruction by Engineer.	8.241	Cum.				
6	PCC M15 for RCC (1:2:4) in foundation and floors with cement sand and crussed aggregate of 10mm to 38mm gauge including miximn with mixture machine and , laying in line & level with curing all type of works complete as per specification & instruction.	1.587	Cum.				
7	Torsteel reinforcement bar for R.C.C. work with cutting, bending, binding & laying with all complete.	99.663	Kgs				
8	Supplying & fixing plywood formworks in perfect line & level with timber props,leveling,centring,fixing ,strapping as per drawing & instruction all complete.	6.955	Sqm				
9	12.5 mm. thick cement sand plaster work (1:4 ) on wall and floor etc.	426.976	Sqm				
10	12.5 mm. thick cement sand plaster work (1:3 ) on ceiling area.	159.951	Sqm				
11	3 mm. thick neat cement punning work	43.317	Sqm				
12	Supplying and fixing of 16 gauge MS sheet with 50x50*5mm MS angle Gate all completw work.	114.800	Kgs				
13	Supplying and fixing of 26 gauge (41MM thich) Colour CGI Sheet Roof Cvering work all completw.	27.500	Sqm				
14	Supplying and fixing of 2" dia.Black pipe truss for staircase roof Cvering work all completw.(M) 3.93kg/rm	78.600	Kgs				
<b>Total cost Rs.</b>							

Name of firm Address :-  
Sign.

Stamp of firm