

“काम छोडाऔ, स्कूल पठाऔ”

श्रीपुराज सामुदायिक विकास केन्द्र, सप्तरी
SHRIPURRAJ COMMUNITY DEVELOPMENT CENTER (SCDC) SAPTARI
Kushaha-2, Saptari

भवन निर्माण कार्य सम्बन्धी शिलबन्दी बोलपत्र आव्हान सम्बन्धी सुचना

सुचना नं २०८१/०८२/०५

(पहिलो पटक प्रकाशित मिति २०८२/०३/०१)

१. श्रीपुराज सामुदायिक विकास केन्द्र, सप्तरी गैर सरकारी तथा गैर नाफामुलक संस्था हो, द फिडम फण्डको आर्थिक सहयोगमा संस्थागत विकास अन्तरगत यस संस्थाको कार्यालयको भवन निर्माण कार्य गर्नु पर्ने भएको, उल्लेखित कार्यको लागि इजाजत प्राप्त इच्छुक फर्म/संस्था/निर्माण कम्पनीहरूको लागि देहायको शर्तहरूको अधिनमा रही तोकिएको समयभित्र रितपूर्वकको पहिलो पटक १५ दिने बोलपत्र आव्हानको सुचना प्रकाशित गरिएको छ ।

बोलपत्रको विवरण

प्याकेज नं.	निर्माण कार्य	शिलबन्दी बोलपत्र					
		लागत अनुमान रकम मु.अ.कर वाहेक	जमानत	दस्तुर रु (फिर्ता नहुने)	मान्य हुने अर्बिध	अन्तिम मिति र समय	खोल्ने मिति र समय
२०८१/०८२/०५	संस्थाको भवन निर्माण ग्राउण्ड	५,४९८,५७९	१६२,५५७			२०८२/०३/१६	२०८२/०३/१६ दिनको २:००बजे

शर्तहरू :

१. शिलबन्दी बोलपत्र फारम प्रथम पटक सुचना प्रकाशित भएको मितिले १५ औं दिनभित्र कार्यलय समयमा नविकरण भएको फर्मको सही छाप, सही गरिएको र लाहा छाप भएको बोलपत्र श्रीपुराज सामुदायिक विकास केन्द्र (SCDC), सप्तरीको सम्पर्क कार्यालय खडक नगरपालिका-६, कल्याणपुर सप्तरीमा मिति २०८२/०२/४ गते ४:०० बजे भित्र बुझाउनु पर्नेछ । तोकिएको समयभित्र नआएको बोलपत्रलाई मान्यता दिइने छैन । स्पष्टसँग बुझिने गरी खामको बाहिरपट्टि मैटल सिल बीन भनी उल्लेख गरिएको हुनु पर्नेछ । यो बोलपत्र मिति २०८२ साल जेष्ठ २१ गते अपरान्ह १.०० बजे खोल्ने छ ।

२. शिलबन्दी दरभाउपत्रको प्रत्येक पानाममा सहिछाप गरि दरभाउपत्र साथ तपसिलमा उल्लेखित कार्यको लागि तपसिल बमोजिमका धरौटी रकम यस कार्यालयको नाममा रहेको रा.वा.बैंक लहान शाखामा रहेको २२६०१००००१८४२००१ (धरौटी) खातामा जम्मा गरेको सक्कल भौचर वा सो वरावरको कम्तीमा १०(नब्बे) दिन म्याद भएको बैंक जमानी पत्र -विड वण्ड) संलग्न राखी यस कार्यालयमा प्रथम पटक सुचना प्रकाशन भएको १६ औ दिनको १२:०० बजे भित्र दर्ता गर्नुपर्ने छ ।

३. प्रथम पटक सुचना प्रकाशित भएको मितिले १६ औ दिनको २:०० बजे भित्र दरभाउपत्र दाता वा निजको प्रतिनिधीको रोहवरमा खोलिनेछ । दरभाउपत्र दाता वा प्रतिनिधी उपस्थिती नभएमा दरभाउपत्र खोल्न बाधा पर्ने छैन । दरभाउपत्र खरि वा दाखिला गर्ने अन्तिम दिन सार्वजनिक बिदा परेमा उक्त दिनको लगत्तै(कार्यालय खुलेको दिन) सोहि समयभित्र दाखिला गर्न सकिनेछ ।

४. बोलपत्र पेश गर्दा प्रत्येक आइटममा अंक र अक्षर दुवैमा प्रष्ट लेखनुपर्छ । जम्मा जोड गरेको रकम लेख्नु पर्नेछ । दररेट मात्र लेखी बोलपत्र बुझाएमा उक्त बोलपत्र रद्द गरिनेछ ।

५. रित नपुगी आएका वा म्याद गुज्री आएको वा शर्त राखि केरमेट गरिएको तथा टिपेक्स लगाएको बोलपत्रलाई मान्यता दिइने छैन ।

६. बोलपत्रलाई पुर्ण वा आंशिक रुपमा स्विकृती गर्ने वा रद्द गर्ने अधिकार यस कार्यालयमा निहित हुने छ ।

७. बोलपत्र फारमको साथमा आपुर्ती कर्ताले निम्न कागजातहरू पेश गर्नु पर्ने छ ।

i. फर्म/निर्माण कम्पनीको दर्ता प्रमाण पत्रको प्रतिलिपी

“काम छोडाऔ, स्कूल पठाऔ”

श्रीपूराज सामुदायिक विकास केन्द्र, सप्तरी
SHRIPURRAJ COMMUNITY DEVELOPMENT CENTER (SCDC) SAPTARI
Kushaha-2, Saptari

ii. आ.व. २०८०/२०८१ को कर चुक्ताको प्रमाण पत्रको प्रतिलिपी

iii. PAN /VAT मा दर्ता भएको प्रमाण पत्रको प्रतिलिपी

८. थप जानकारीको लागि कार्यालय समभित्र कार्यालयको टेलिफोन नम्बर ०३१-५४०४१२ मा सम्पर्क गर्न सकिनेछ ।
यो सुचना यस कार्यालयको Website : www.shripurraj.org.np मा समेत प्रकाशन गरिएको छ ।

९. यस कार्यालयले प्रतिपादन गरेको आचारसंहिता तथा निति नियमहरु आपूर्ति कर्ताले पालना गर्नु पर्ने छ ।

फर्म/ निर्माण कम्पनीके नाम:

सप्लायरको नाम :

टेलिफोन नम्बर :

दस्तखत :

ठेगाना :

मिति तथा छाप :

Shripurraj Community Development Center (SCDC) for office building						
Surunga-6, Saptari						
Bill of Quantities						
SL.No	Item Discription	Unit	Quantity	Bidder's Rate in (NRP)	Bidder's Rate (in Words)	Total Amount (NRP)
A.	Civil Work					
1	Site Clearance before after completion of work including disposing the remaining construction materials & making site working condition all complete as per drawing and specification	Ls	1			0
2	E/W in exaction for preparation of site and foundation work all complete(Boulder Mix soil)	M3	118.51			0
2.1	Back filling of ordinary soil by spreading it in the layer of 15-15 CM ,sprinking water and then compacting with the help of labour including hauling distance up to 10 MM all complete	M3	150.62			0
3	flat dry brick soiling in foundation and floor including sand filling in joints,leveling, ramming etc all complete	M2	214.65			0
3.1	First class local chimney made by brick work in cement, sand mortal (1:4)in superstructure in perfect line and level including wetting the brick,packing the joints and curing all types of works as per specification and instruction by Engineer)	M3	44.33			0
4	First clas local Chimney made brick work in cemenet sand mortar(1:4) in superstructure in perfect line and level including wetting brick,packing the joints and curring all types of works as per specificatin and intstruction by Engineer	M3	14.2			0
4.1	Plain cement concret PCC M10,(1:3:6) work in foundation and floors with cement,sand and crussed aggregate f 10MM t 38mm guage including mixetre machin & compaction by vibrator,laying in line & level with curing etc all complete as per design, drawing and specification.	M3	4.78			0
5	Plain cement concret(PPC) in (1:2:4) ratio M15 for PCC works in Room Floor with approved quality of cement ,sand and stone aggregate including mixing, laying, compacting and curing etac all complete as per design, drawing and specification.	M3	11.56			0
5.1	plain cement concrete(PCC) in 1:1:5:3 ratio (M20) for RRC works in column,beam, slab etc. with approved quality of cement, sand and stone aggreahte including mixing.laying, compacting and curing etc all complete as per design, drawing and specification	m3	76.51			0

Authorized signature

Office Stamp

6	Steel reinforcement bar of Fe 415/500 grade including, straightening, cleaning, cutting, bending, placing in position and binding with annealed binding wire all complete as per design, drawing and specification.	Kg	8470.72			0
7	Formwork, shutting, centering with plywood and wooden post necessary propping, scaffolding, staging, supporting and removal etc all complete in perfect line and level as per design, drawing and specification.	M2	413.2			0
8	Supplying and fixing seasoned sal wood chaukhat 125mm*75mm) size as per drawings, specification and instructions of site engineers all complete	M3	0.4			0
9	supplying and fixing aluminium sliding window without ventilator from section.	M2	43.13			0
10	Supplying and fixing of flush doors with seasoned sal wood frame (65mm*35mm size) 19mm thick water proof plywood grooved and properly fixed as per drawings, hinges 3*6 inch, screws lcking 12 inch, heavy, handle grip 6inch alumunium, cheskini 6 inch aluminium etc specificattin and instructions of site engineer, all complete	M2	17.79			0
	Sub-Total					
B	Electrical worl					
	5% of civil work(DB Box,Wires, Fan, Bulbs, Power socket					
	Sub-Total					
C	Sanitary work					
	3% of civil work (plumbing 1.5 inch, outlet tap-4, pan sheet-2, wash basin-2)					
	Sub-Total					
	Total					

.....
Authorized signature

Office Stamp